

**Notice inviting quotation for renovation of computer Cell
at 7-9 Aram Bagh, Paharganj, Delhi**

Sealed quotations are invited from contractors/firms registered with DSCSC, CPWD, PWD, DDA, DSIIDC, DAMB, DTTDC, NDMC, MCD providing and laying Wall finishing, flooring and cladding work for renovation of computer cell at 7-9, Aram Bagh, Pahar Ganj, Delhi.for renovation of Computer Cell.

The estimated cost is Rs.1,33,672/-. The tender document can be downloaded from the DSCSC's website www.dscsc.delhigovt.nic.in.

Sealed quotations duly filled up alongwith earnest money of **Rs.2,673/-** in the form of DD/Payorder in favour of DSCSC Ltd. payable at Delhi may be submitted upto 2.30 PM on 23.05.2011 and the same shall be opened on 23.05.2011 at 3.00 PM in the presence of the tenderer or their authorised representative who may like to be present.

CMD, DSCSC reserve the right to accept of reject any/ all quotations without assigning any reason whatsoever.

(R.P.SEHGAL)
CO.SECY-CUM-AGM

DECLARATION

1) The particulars furnished above are true to the best of my/our knowledge and belief & no material fact has been concealed therein and I/We understand that concealment of material facts shall entitle the Corporation to take penal action including blacklisting/debarring the applicant from participating in tender of the Corporation for a period upto 5 years.

2) I /We shall not withdraw the rates quoted by me/us during the tender process.. In the event of work awarded to me/us and in case failure to execute the work, the corporation shall be entitled to forfeit earnest money deposited by me/us. & the Corporation shall also be entitled to get the work done from any other contractor at my/own risk & cost.

(Signature of applicant)

Name.....
(In full) & status

Conditions

1. Contractors/firms should be registered with VAT Deptt. for works contract.
2. Contractors/firms should be registered with 'Service Tax Deptt'.
3. The Contractor will submit requisite earnest money i.e Rs. 2,673/- alongwith tender.
4. TDS/VAT and other taxes will be deducted from the bill of Contractor as per prevailing rates/rules etc.
5. The work shall be completed within a period of 20 days after award of work.
- 6.. The Corporation will impose penalty @ Rs.500 per day, if the work is delayed beyond the stipulated period. However the Contractor may request Co. Secy-cum-AGM for extension of period if the reasons are genuine..
7. 10% Security will be deducted from the contractor's bill & the same will be released after defect liability period of 6 (Six) months from the date of completion of work.
8. The contractor shall take all precautions and safety measures for all workers/labourers etc. which are to be engaged by the Contractor for execution of said work.
9. The work shall be executed with high degree of workmanship & confirm to the approved norms, standard and specification for the materials and workman ship.
10. The required work shall be carried out on continuous basis while the normal functions of the corporation's at site will continue as usual till the works are carried out.
11. The payment will be made to contractor after completion of work. However management of the Corporation may consider running payment
12. The rates of items of work shall be applicable for all height and depth otherwise specified in the item.
13. The contractor shall be responsible to arrange T & P and water etc required for execution of work. No payment shall be made to the contractor for damage caused by rains or other natural calamities or riots during execution of work and no claim on this account will be entertained/admissible
14. The CMD, DSCSC Ltd. reserves the right to reject any or all the tenders without assigning any reason whatsoever.

Name of work:-Providing and laying Wall finishing, flooring and cladding work for renovation of computer cell at 7-9, Aram Bagh, Pahar Ganj, Delhi

S.No	Description of work	Unit	Quantity	Rate	Amount
A) WALL FINISHING					
1.01	Providing and applying 3 coats of Acrylic Emulsion paint of approved colour and shade to internal walls and ceiling after thoroughly sand papering surfaces to remove dust, dirt etc. and repairing dents, cracks, holes with POP to achieve level surface and finishing with two coats of primer, putty and three coats of paint including cost of material, labour, scaffolding etc. all complete as directed by the Engineer in charge. Rate to include application at all heights and levels, surfaces and textures as approved by Architect.	Sqm.	121.00 Sqm.		
B) FLOORING & CLADDING WORKS					
2.01	Providing and fixing 2 mm thick recycled PVC slip resistance vinyl sheet flooring with PUR of approved colour & shade of polyflor for range Prestige or equivalent make having wear resistance of Group 'P' as per EN 660-2 and should have a residual indentation of < 0.10mm confirming to EN433. The vinyl sheet shall be laid & fixed with any water based adhesive preferably AROBOND-44 of M/s. Colour bond make or VC 31 of M/s. Pidilite ind. or any other make as per manufacturer's specification as per direction and to the entire satisfaction of Engineer-in-charge complete. The laid flooring shall confirms the slip resistance as per AS/NZS 4586 on testing to 'B' rating for wet/bare foot ramp and R10 rating for oil wet ramp as well as fire resisting rating '6' of AS 1530.3 for spread of flame & smoke developed.	Sqm.	57 Sqm.		

2.02	Extra for Providing and laying a layer of cementitious salt smoothing compound Ardex CL-11 of 3 mm average thickness over a concrete surface applied with Ardex P-51 priming compound as per manufacturer's recommendation to provide a smooth & homogenous surface for laying of vinyl sheet flooring complete to the entire satisfaction of Engineer-in-charge.	Sqm.	57 Sqm.		
------	---	------	---------	--	--