

DELHI STATE CIVIL SUPPLIES CORPORATION LTD.
7-9, ARAM BAGH, PAHAR GANJ, NEW DELHI – 110 055.

F. 2 (4) 2011/DSCSC

Dated:-

To,

Sub:- Inviting of sealed Quotation.

Sir,

This Corporation intends to get the below mentioned work. Tender documents are also available on DSCSC's website www.dscsc.delhigovt.nic.in.

Sr. No.	Name of work	Estimated Cost	Earnest money	Time of completion
1.	Providing & laying Brick work, plaster work, window work, glass partition work, electrical work for renovation of computer cell at 7-9, Aram Bagh, Pahar Ganj, Delhi	Rs. 1,91,163/-	Rs. 3,823/-	20 days.

Interested contractors/firms registered with 'Service Tax Department' may submit sealed quotation upto 14.06.2011 by 2.30 PM along with earnest money of Rs. 3,823/- in the shape of DD/Pay order in favour of DSCSC Ltd. The quotation without earnest money will not be accepted.

The quotation will be opened in the presence of tenderers or their authorized representative who may like to present on the same day i.e 14.06.2011 at 3.00 PM. The contractor can see the site before quoting the rates. After award of work the contractor refuse to execute the work, the Corporation will forfeit his / their earnest money. The Competent Authority reserve the right to reject to any or all the quotation without assigning any reason whatsoever.

(K.K.NIGAM)
SR. MANAGER

Encl.:- As above

PARTICULAR OF TENDERER/QUOTATIONER

1) NAME OF THE APPLICANT :
FIRM (In full and in block letters)

2) Address (In Block Letters) :
Pin code
Phone nos.

3) Constitution of the firm Whether :
proprietor or Partnership or
Cooperative society or Company.
Details of proprietor or partners or
Directors i.e. their address,
Telephone numbers, (Attested
copies of partnership Deed. Form A
& Form B to be enclosed)

4) Whether registered in DSCSC, :
CPWD,PWD, DDA, DSIIDC,DAMB,
DTTDC, NDMC, MCD

5) Service tax Registration No.
Name as per service tax registration
certificate

6) DVAT Registration No. :
Name as per DVAT Certificate

7) Permanent Account No.

8) Whether any
partner/proprietor/firm convicted by
any court of law. if so give details.

9) Name of work :
:

10) The amount of earnest money
deposited in favour of DSCSC Ltd in
shape of DD/Pay order no, date &
the schedule bank on which drawn.

DECLARATION

1) The particulars furnished above are true to the best of my/our knowledge and belief & no material fact has been concealed therein and I/We understand that concealment of material facts shall entitle the Corporation to take penal action including blacklisting/debarring the applicant from participating in tender of the Corporation for a period upto 5 years.

2) I /We shall not withdraw the rates quoted by me/us during the tender process.. In the event of work awarded to me/us and in case failure to execute the work, the corporation shall be entitled to forfeit earnest money deposited by me/us. & the Corporation shall also be entitled to get the work done from any other contractor at my/own risk & cost.

(Signature of applicant)

Name.....
(In full) & status

Conditions

1. Contractors/firms should be registered with 'Service Tax Deptt'.
2. The Contractor will submit requisite earnest money i.e Rs. 3,823/- alongwith tender.
3. TDS/VAT and other taxes will be deducted from the bill of Contractor as per prevailing rates/rules etc.
4. The work shall be completed within a period of 20 days after award of work.
5. The Corporation will impose penalty @ Rs.500 per day, if the work is delayed beyond the stipulated period. However the Contractor may request Co. Secy-cum-AGM for extension of period if the reasons are genuine..
6. 10% Security will be deducted from the contractor's bill & the same will be released after defect liability period of 6 (Six) months from the date of completion of work.
7. The contractor shall take all precautions and safety measures for all workers/labourers etc. which are to be engaged by the Contractor for execution of said work.
8. The work shall be executed with high degree of workmanship & conform to the approved norms, standard and specification for the materials and workman ship.
9. The required work shall be carried out on continuous basis while the normal functions of the corporation's at site will continue as usual till the works are carried out.
10. The payment will be made to contractor after completion of work. However management of the Corporation may consider running payment
11. The rates of items of work shall be applicable for all height and depth otherwise specified in the item.
12. The contractor shall be responsible to arrange T & P and water etc required for execution of work. No payment shall be made to the contractor for damage caused by rains or other natural calamities or riots during execution of work and no claim on this account will be entertained/admissible
13. The CMD, DSCSC Ltd. reserves the right to reject any or all the tenders without assigning any reason whatsoever.

Name of work :-Providing & laying Brick work, plaster work, window work, glass partition work, electrical work for renovation of computer cell at 7-9, Aram Bagh, Pahar Ganj, Delhi

S.No	Description of work	Unit	Quantity	Rate	Amount
A) BRICK WORK					
1.01	Brick work with FPS bricks of class designation 75 in super structure above plinth level in all shapes and sizes in :				
	Cement mortar 1:6 (1cement : 6 coarse sand)	Cum	1.00 Cum		
B) PLASTER WORK					
2.01	Providing and applying 12mm thick (average) premixed formulated one coat gypsum lightweight plaster having additives and light weight aggregates as vermiculite/perlite respectively conforming to IS: 2547 (Part-I & II) 1976, applied on hacked/uneven background such as bare bricks/ block/ RCC work on walls & ceiling at all floors and location, finished in smooth line and level etc. complete.	Sqm.	4.00 Sqm.		
C) WINDOW WORKS					
3.01	Providing and fixing factory made UPVC window unit consisting of frame or window shutter of presting white high impact modified window UPVC extruded section conforms to B.S. 7413 having an over all dimensions as below (tolerance $\pm 0.5\text{mm}$ with wall thickness $2.4\text{mm} + 0.5\text{mm}$, corners of the window frame transom and mullion sections with joints mitred and fusion welded. All excess material is to be neatly trimmed and neatly feature grooved/ raised nib finish so that the route of drainage is prevented from passing through the reinforcement chamber . The side vertical of the frames reinforced by galvanised M.S. / Aluminium profiles 1.5 to $3\text{mm} \pm 0.1\text{mm}$ wall thickness with hinges and accessories as required complete as per manufacturer specification and satisfaction of engineer incharge manufacturer will give warantty of 10 years on profile & one years on hard ware. Cost of window includes cost of glass $8\text{mm}(4+1.52+4)$ thick toughened+ 12 mm dry air gap + 6mm thick clear toughened glass, excluding cost of 1.52mm thick designer poly vinyl butyl inter layer sandwiched between two glasses. (a) Extruded section profile of size $65\text{mm} \times 58$ mm & sash size of $45\text{mm} \times 90\text{mm}$ with 2 track sliding window with unit of size more then 2400mm .	Sqm.	3.6 Sqm.		

S.No	Description of work	Unit	Quantity	Rate	Amount
(b)	Extra for 3 track with fly screen mesh over window (a).	Sqm.	3.6 Sqm.		
D)	GLASS PARTITION WORK				
4.01	Providing and fixing frame less glazing butt jointed using clear weather silicone with 13.5 mm thick clear toughened laminated glass comprising of 6mm thick clear toughened glass + 1.52mm Poly vinyl butyl interlayer + 6mm thick clear toughened glass including aluminum U channels of 38mm x 38 mm x 3 mm as frame member fixed at top & bottom fixed to the lintel/beams & flooring respectively with suitable fastners etc. complete as per drg. to the entire satisfaction of Engineer-in-charge. Allowance to be made for movement at sill and jambs by neoprene gaskets and joint between plates are weatherproofed with a silicone base sealant of approved make including performing mockup and field test for air and water infiltration etc. all confirming to relevant standards at site.	Sqm	15.00 Sqm.		
4.02	Extra over item 4.01 for providing and fixing glass door shutters in opening of glazed partitions with stainless patch fittings including floor door springs, SS handle size 25mm x 650mm, locking arrangement of Carl F or equivalent or better quality as approved by Engineer-in-charge. [Area of glazed door shutter partition to be measured for payment.]	Sqm	3.10 Sqm.		
4.03	Extra over item 4.01 for providing and fixing 1.52mm thick designer poly vinyl butyl inter layer sandwiched between two glasses in glazed partitions wherever required as per approved design and pattern to the entire satisfaction of Architect.	Sqm	3.1 Sqm.		
E)	DISMANTLING WORKS				
5.01	Dismantling door, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 m lead:				
a)	Of area 3 sq. metres and below	Each	5 Nos		

S.No	Description of work	Unit	Quantity	Rate	Amount
F)	ELECTRICAL WORKS				
6.01	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FR PVC insulated copper conductor single core cable in surface / recessed PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FR PVC insulated copper conductor single core cable etc as required.				
	a) Group C	Point	15 Point		
6.02	Wiring for light/ power plug with 2X4 sq.mm FR PVC insulated copper conductor single core cable in surface recessed PVC conduit alongwith 1 No. 4 sq.mm FR PVC insulated copper conductor single core cable for loop earthing as required.	Metre	20 Metre		
6.03	Wiring for light/ power plug with 4X4 sq.mm FR PVC insulated copper conductor single core cable in surface/ recessed PVC conduit alongwith 2 Nos. 4 sq.mm FR PVC insulated copper conductor single core cable for loop earthing as required.	Metre	50 Metre		
6.04	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FR PVC insulated copper conductor, single core cable in surface/ recessed PVC conduit as required.				
	(a) 2 X 1.5 sq.mm + 1 X 1.5 sq.mm earth wire.	Metre	10 Metre		
6.05	Supplying and fixing of following sizes of PVC conduit along with accessories in surface/ recess including cutting the wall and making good the same in case of recessed conduit as required.				
	(a) 20 mm	Metre	20 Metre		
6.06	Supplying and fixing following modular switch/socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
	(a) Telephone socket outlet.	Each	15.00 Nos.		
	(b) T.V. Antena socket outlet	Each	15.00 Nos.		
6.07	Supplying and fixing following size /modules, GI box along with modular base & cover plate for modular switches in recess etc. as required.				
	a) 1 or 2 Module (75 mm X 75 mm)	Each.	30 Nos.		
6.08	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 15/16A & 5/6A modular socket outlet and 15/16A modular switch, connection, painting etc. as required.	Each	10 Each		

S.No	Description of work	Unit	Quantity	Rate	Amount
6.09	Supplying and drawing co-axial TV cable RG-6 grade, 0.7 mm solid copper conductor PE insulated, shielded with fine tinned copper braid and protected with PVC sheath in the existing surface/ recessed steel/ PVC conduit as required.	Metre	15 Metre		
6.10	Supplying and drawing CAT6 data cable in the existing conduite including connection etc. as required.	Metre	50 Metre		
6.11	Supplying and fixing wall Mounting T5 Lamp for Task/accent light Bajaj make with installation, testing and commissioning of fluorescent fitting, complete with all accessories and tube etc. directly on ceiling/ wall, including connection with 1.5 sq.mm FR PVC insulated, copper conductor, single core cable and earthing etc. as required, and directed/approved by the Architect.	each.	10 each.		

